



**KAUIKEAOULI HALE SIXTH FLOOR**

0 4 8 16 32 FT  
 FORMATTED TO PRINT ONTO 11" x17" SHEET SIZE

**NOTES**

- 1. INDICATES AREA OF CARPET TO BE REMOVED AND RECARPETED INCLUDING ACCESSORIES - 24x24 CARPET TILES, QUARTER-TURN INSTALLATION
- 2. REMOVE EXISTING BASE AND PROVIDE NEW RESILIENT BASE THROUGHOUT CARPET AREA
- 3. PROVIDE RESILIENT TRANSITION STRIPS TO OTHER EXISTING FLOORCOVERING MATERIALS TO REMAIN
- 4. LOCATIONS OF WALLS, DOORS AND OTHER PLAN FEATURES ARE APPROXIMATE
- 5. FOR ACCURATE DIMENSIONS, DO NOT SCALE DRAWINGS - CONTRACTOR IS RESPONSIBLE TO TAKE ACCURATE FIELD MEASUREMENTS
- 6. IF ASBESTOS-CONTAINING MATERIALS ARE FOUND OR SUSPECTED, STOP WORK IMMEDIATELY AND NOTIFY CONTRACTING OFFICER
- 7. FOR EXISTING CARPET TILES TO BE REMOVED AND PROVIDED TO OWNER, SEE ATTACHMENT C

**KAUIKEAOULI HALE - RECARPET SIXTH FLOOR**  
**JUDICIARY PROJECT IDENTIFIER 2021-07-059**

**ATTACHMENT A**  
**CARPET PLAN**

APRIL 5, 2021